



American Test Lab, Inc.  
1656 Calvert Road, Brevard, N. C. 28712  
Phone (828) 884-3700 Fax (828) 884-3710  
Web [www.atlnc.com](http://www.atlnc.com) E-Mail [atli@citcom.net](mailto:atli@citcom.net)

ATLNC # 0521.01-12

Report Date: 6/21/12

Test Date: 05/21/12

ATLNC Certification # 08-0227.14

FL Organizational # TST 1555

**Test Requested By:** Metal Roofing Systems  
7687 Mikron Drive  
Stanley, NC 28164  
Phone 704-820-3110

**Test Standards:** ASTM E 1592-05

**Test Conditions:** 70-75 degrees F

**Description of product tested:**

**Specimen A,** 24 gauge (.026") Galvalume Metal Roof Panels over 3-1/2" x 8" x 16 ga. (.061") Z purlins as shown in MRS System 2000 dwg 1 - 4. The edge and the ends of the panels were attached to the purlins with self drilling screws.

**Specimen B,** 24 gauge (.026") Galvalume Metal Roof Panels over 3-1/2" x 8" x .061" Z purlins as shown in MRS System 2000 dwg 1 - 4. The edge and the ends of the panels were attached to the purlins with self drilling screws.

**Configuration:** Specimens Mounted vertically in steel test chamber  
Specimen A, (2) 5' purlin spans, 4 panels wide  
Specimen B, (4) 1' purlin spans, 4.5 panels wide

**Description of Units:**

**Specimens A, B**

**Panel Construction-** 24 ga (.026") Galvalume steel roof panels 16" wide with 1-3/4" interlocking standing seams per MRS System 2000 dwg 1 - 4. Specimen A -138" long, Specimen B - 72" long

**Purlin Construction-** 3-1/2" x 8" x 16 ga (.061") Z purlins

**Purlin Spacing-** Specimen A 2 spans 60" OC with 8" overhang.  
Specimen B 4 spans 12" OC with 12" over hang

### Screws and Method of Attachment-

**Purlins-** 18 ga clips attached to purlins with 2 self drilling screws as shown in drawing.


**Panel Standing Seams-** Overlaps were 16" OC and panels were attached with 18 ga clips at each purlin as shown in drawing.

**Purlin Attachment-** Each purlin was attached to the chamber.


### Test Specimens

Indicator Locations

Specimen A



Specimen B



\*Drawings not to scale.

### Specimen A

Deflections in inches

Pressure Increments psf Positive	Time (sec)	End Purlin Between Ribs (A)	Perm. Set	Mid- Span Rib (B)	Perm. Set	Mid-Span (C)	Perm. Set
*RZ 5.6	60						
8	60	.05"	.08"	.01"	.00"	.09"	.01"
12	60	.09"	.08"	.03"	.00"	.16"	.01"
16	60	.11"	.08"	.04"	.00"	.22"	.01"
24	60	.12"	.10"	.06"	.01"	.28"	.02"
28	60	.14"	.10"	.09"	.01"	.37"	.03"
32	60	.14"	.11"	.09"	.01"	.37"	.04"
36	60	.15"	.10"	.11"	.02"	.48"	.05"


### Deflections in inches

Pressure Increments	Time (sec)	Mid Span Rib (D)	Perm Set	End Span Purlin mid panel (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
*RZ 5.6	60						
8	60	.02"	.01"	.01"	.01"	.09"	.01"
12	60	.05"	.02"	.03"	.01"	.16"	.01"
16	60	.08"	.03"	.03"	.01"	.22"	.01"
24	60	.11"	.04"	.04"	.02"	.28"	.02"
28	60	.15"	.03"	.06"	.02"	.37"	.03"
32	60	.15"	.05"	.06"	.02"	.37"	.04"
36	60	.18"	.07"	.07"	.02"	.42"	.05"

**\*Note:** RZ (Reference Zero pressure) is to compensate for vertical test position.

**Note:** C indicator reading is used as Total Panel Deflection and Permanent Set.

### Positive Side Graph



**Observations:** Deflections increased as pressure increased. No fastener failure occurred.

### Deflections in inches


Pressure Increments psf Negative	Time (sec)	End Purlin Between Ribs (A)	Perm. Set	Mid-Span (B)	Perm. Set	Mid-Span (C)	Perm. Set
*RZ 5.6	60						
8	60	.03"	.01"	.12"	.05"	.33"	.05"
16	60	.06"	.01"	.17"	.09"	.61"	.08"
24	60	.07"	.02"	.32"	.12"	.83"	.11"
32	60	.10"	.02"	.42"	.17"	1.05"	.15"
40	60	.12"	.03"	.56"	.20"	1.26"	.18"
48	60	.13"	.04"	.87"	.27"	1.61"	.28"
56	60	.17"	.07"	1.30"	.33"	2.05"	.40"

Pressure Increments psf Negative	Time (sec)	Mid Span (D)	Perm Set	End Span Purlin mid panel (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
*RZ 5.6	60						
8	60	.11"	.03"	.40"	.06"	.33"	.05"
16	60	.19"	.05"	.73"	.16"	.61"	.08"
24	60	.28"	.07"	.10"	.17"	.83"	.11"
32	60	.39"	.14"	1.23"	.23"	1.05"	.15"
40	60	.56"	.16"	1.5"	.31"	1.26"	.18"
48	60	.75"	.19"	1.95"	.46"	1.61"	.28"
56	60	1.07"	.27"	2.48"	.53"	2.05"	.40"

**\*Note:** RZ (Reference Zero pressure) is to compensate for vertical test position.

**Note:** C indicator reading is used as Total Panel Deflection and Permanent Set.

### Negative Side Graph



**Observations-** Deflections increased as pressure increased. Fastener failure occurred at approximately 57 to 58 psf. The panel disengaged from the clips.

### Specimen B

Deflections in inches

Pressure Increments psf Positive	Time (sec)	Purlin Mid Panel (A)	Perm. Set	Mid-Span (B)	Perm. Set	Mid-Span (C)	Perm. Set
*RZ 5.6	60						
12	60	.02	.01	.03	.02	.01	0
24	60	.03	.01	.04	.02	.03	0
36	60	.03	.01	.05	.03	.04	0
48	60	.03	.01	.06	.03	.05	0
60	60	.03	.01	.07	.03	.06	0
72	60	.03	.01	.07	.03	.07	0
84	60	.03	.00	.08	.03	.08	.0
96	60	.03	.00	.08	.03	.10	.0

### Deflections in inches


Pressure Increments psf Positive	Time (sec)	Mid Span (D)	Perm Set	Purlin mid panel (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
RZ 5.6	60						
12	60	.03	.02	.02	.01	.01	0
24	60	.04	.02	.03	.01	.03	0
36	60	.05	.03	.04	.01	.04	0
48	60	.06	.03	.05	.02	.05	0
60	60	.07	.03	.05	.02	.06	0
72	60	.07	.03	.06	.02	.07	0
84	60	.08	.03	.06	.02	.08	.0
96	60	.08	.03	.06	.03	.10	.0

**\*Note:** RZ (Reference Zero pressure) is to compensate for vertical test position.

Note: C indicator reading is used as Total Panel Deflection and Permanent Set.

**Observations-** Deflections increased as pressure increased. No fastener failure occurred.

### Positive Side Graph



### Deflections in inches

Pressure Increments psf Negative	Time (sec)	Purlin Mid Panel (A)	Perm. Set	Mid-Span (B)	Perm. Set	Mid-Span (C)	Perm. Set
RZ 5.6	60						
21	60	.16	.04	.06	.01	.15	.06
42	60	.26	.05	.08	0	.25	.25
63	60	.36	.08	.10	0	.34	.09
84	60	.44	.07	.11	0	.41	.09
105	60	.51	.08	.11	.01	.48	.09
126	60	.56	.08	.12	.01	.53	.09
147	60	.65	.10	.13	.02	.59	.09
168	60	.70	.11	.13	.03	.67	.09
189	60	.78	.11	.15	.03	.72	.09
210	60	.90	.12	.20	.03	.84	.10

# Deflections in inches


Pressure Increments psf Negative	Time (sec)	Mid Span (D)	Perm Set	Purlin Mid Panel (E)	Perm. Set	Total Panel Deflection	Total Panel Perm. Set
RZ 5.6	60						
21	60	.10	.05	.17	.09	.15	.06
42	60	.14	.06	.32	.15	.25	.25
63	60	.18	.07	.41	.17	.34	.09
84	60	.22	.08	.49	.18	.41	.09
105	60	.24	.08	.56	.19	.48	.09
126	60	.28	.09	.61	.19	.53	.09
147	60	.32	.09	.68	.20	.59	.09
168	60	.35	.11	.74	.20	.67	.09
189	60	.38	.12	.80	.20	.72	.09
210	60	.43	.13	.92	.21	.84	.10

**\*Note:** RZ (Reference Zero pressure) is to compensate for vertical test position.

**Note:** C indicator reading is used as Total Panel Deflection and Permanent Set.

**Observations-** Deflections increased as pressure increased. No fastener failure occurred.

## Negative Side Graph



Note: 2 mil polyethylene film was used for the ASTM 1592 test, it is the opinion of the undersigned that it had no influence on the results of the test.

Observers-

Keith Owen / ATL  
Eddie Lance, Josh Thomas / ATL  
Jeremiah Buechner / Metal Roofing Systems  
Andy Sigmon / Metal Roofing Systems  
Brian Thompson / Metal Roofing Systems  
David W. Johnson, P.E

Keith Owen, Lab Manager  
American Test Lab, Inc.

*Keith Owen*  
6/21/12

All Tests Witnessed and Certified by:

David Johnson P. E.  
1656 Calvert Rd.  
Brevard, NC 28712  
Florida P.E. # 00061915

Engineer Seal And Signature

*David Wesley Johnson*  
6/21/12



Certificate of Independence: The witnessing engineer has no equity interest in American Test Lab of North Carolina, Metal Roofing System or their parts vendors. Witnessing engineer is in complete compliance of Florida Statue 9B-72, Section 72.110


Disclaimer:

ATL and its staff have no equity interest in any product tested or installed. This test report was prepared by American Test Lab, North (ATL) for the exclusive use of the above named client; it does not constitute certification of this product. The results are for that particular specimen tested and does not imply the quality of similar or identical products manufactured or installed from specifications identical to the tested product. ATL is a testing lab and assumes that all information provided by the client is accurate and does not guarantee or warranty any product tested or installed. This report may not be reproduced except in full, and only under expressed permission from American Test Lab or Metal Roofing System. Reproduced reports in hard copy must be labeled "Copy".

**AMERICAN TEST LAB  
NORTH**

DATE 6/21/12  
REPORT NO. ATLNC 0521.01-12

*Keith Owen*  
ATL INSPECTOR



24 GA. SYSTEM 2000 SSMR PANEL

$H = 1-7/8''$  $W = 2-1/4''$ 

AMERICAN TEST LAB  
NORTH


DATE

6/21/12


REPORT NO.

ATLNC 0521.01-12

*Keith Owen*  
ATL INSPECTOR




CLIP SIDE VIEW

 $H = 1-7/8''$  $W = 2-1/4''$ 

CLIP FRONT VIEW


SYSTEM 2000 CLIP




**AMERICAN TEST LAB  
NORTH**

DATE 6/21/12  
REPORT NO. ATLNC 0521.01-12

*Kurt Owen*  
ATL INSPECTOR



CLIP SECTION VIEW



AMERICAN TEST LAB

CLIP SIDE VIEW

NORTH

DATE 6/21/12REPORT NO. ATLNC 0521.01-12Keith Owen

ATL INSPECTOR